



The City Of

San Angelo, Texas

Engineering Services Department

72 W College Avenue, San Angelo, TX 76903

Addendum No. 2

TO: ALL PLAN HOLDERS

DATE: February 3, 2017

PROJECT: ES-04-17 Water Line Improvements

The plans of the above referenced project are modified as described below. All bidders shall acknowledge receipt of this and all other addenda on the Bid Form. This addendum becomes a part of the contract documents. All provisions of the original plans, and contract documents shall remain in full force and effect, except as modified by this addendum.

1. Revised Delivery of Proposal

No change.

2. Bid Form

- Clarification on Bid Item No. 4 – 6" RESILIENT SEAT GATE VALVE; replace with 8" RESILIENT SEAT GATE VALVE.
- Clarification on Bid Item No. 14 – FIRE HYDRANT ASSEMBLY; quantity is five (5).

3. Technical Specifications

The following are added to the General Notes as Section 4.1.25:

- All new PVC water pipes shall have tracer wire installed. Tracer wire shall be 14-guage, HDPE-coated cooper/steel wire manufactured for direct burial.
- Approved Manufacturers for tracer wire are: Agave Wire, Copperhead, and Southwire.
- All new PVC water and sanitary sewer pipes shall have detectable marking tape installed. Marking tape shall be 2-inch, color blue for water and green for sewer.
- Approved Manufacturers for detectable tape are: Accucast, Presco, Pro-Line, and Terra Tape.

Addendum No. 2 Issued By:
City of San Angelo - Engineering Services Department


Quang Nguyen, P.E.
Project Engineer



Company Name _____

Price Proposal

RFCSP: ES-04-17/Water Line Improvements

Pursuant to the Foregoing Notice to Respondents, the undersigned respondent hereby proposes to do all work and furnish all necessary superintendence, labor, machinery, equipment, tools, and materials, and whatever else may be necessary to complete all work upon which the proposals, as provided by the attached specifications and shown on the plans, and binds himself on acceptance of this proposal to execute an agreement and bonds according to the accompanying forms, for performing and completing the said work within the time stated, and furnishing all required guarantees, for the following prices to-wit:

Summary					
Item No.	Item Description	Quantity	Units	Unit Cost	Extended Cost
1	16" AWWA DR 13.5 HDPE PIPE	502	LF		
2	8" AWWA C900 CLASS 150 PVC PIPE	5,872	LF		
3	4" AWWA C900 CLASS 150 PVC PIPE	23	LF		
4	6" RESILIENT SEAT GATE VALVE 6" 8"	18	EA		
5	4" RESILIENT SEAT GATE VALVE	1	EA		
6	16"x 16" WET TAP	2	EA		
7	12"x 8" WET TAP	2	EA		
8	8"x 6" WET TAP	1	EA		
9	4" FIRE SERVICE	1	LS		
10	6" FIRE SERVICE	2	LS		
11	2" SERVICE LINE	12	EA		
12	1" SERVICE LINE	75	EA		
13	PARTIAL PLUMBER RELOCATES	3	EA		
14	FIRE HYDRANT ASSEMBLY	5 4	EA		
15	TRENCH SAFETY	6,397	LF		
16	CONTINGENCY	1	LS	\$65,000	\$65,000
				Total	\$
ADD ALTERNATE (REFER TO PLANS W-822A, W-824A AND W-825A)					
Item No.	Item Description	Quantity	Units	Unit Cost	Extended Cost
2a	8" AWWA C900 CLASS 150 PVC PIPE	4,443	LF		
2b	8" AWWA C900 CLASS 235 – DR 18 CERTA LOK PVC PIPE (DIRECTIONAL DRILL OPTION)	1,429	LF		
				Total	\$