



CITY OF SAN ANGELO
PURCHASING DIVISION
72 West College Avenue, San Angelo, Texas 76903
Tel: (325) 657-4219

ADDENDUM 1

Date: July 12, 2018

RFB No: PK-03-18 / Renovation and Expansion of Ruffini Parking Lot

Bid Date: July 19, 2018/2:00 PM Local Time

The following clarifications, changes, additions, and/or deletions are hereby made to the RFB:

- **Will water lines be at a minimum 36" depth?**
Yes, the domestic and irrigation lines will be at a depth of 36". There will be a sweep upwards at each end of the irrigation line to facilitate pulling the actual water line through the 4" sleeve that is to be provided for the irrigation line. The fire line will be at 48" depth.
- **Lay down curb is called for instead of a full curb and gutter. Is this what the City wants?**
The drawings provide only details for standard curb and gutter installations. However, on the interior islands, it would be acceptable to use lay down curbs.
- **Under the alternate to replace the sidewalk along S. Chadbourne, are curb and gutters part of the alternate or is the work to the back of existing curb only?**
The alternate as written states to "Replace existing sidewalk behind curb along Chadbourne Street". This implies that it is only the sidewalk that is to be replaced under this alternate. However, there are areas where the sidewalk has been replaced at some point monolithically with the curb and so the curb would need to be repaired/replaced as part of this work.
- **Under the alternate to infill the curb at the existing alley, will the adjacent sidewalk need to be cut back so grades will work?**
Detail 1/A-101 is a blown up plan detail showing Alt – 1. The work does appear to go back as far as the beginning of the existing sidewalk slope and ramp. Therefore, the alternate would include repairing the sidewalk in this area to work with the rest of the new walk.
- **Please see attached changes to Civil Engineering Drawings.**

For other questions or clarifications, please contact the Purchasing Division at SAPurch@cosatx.us.

Sincerely,

A handwritten signature in blue ink, appearing to read "Chris Webber".

Chris Webber
Purchasing Specialist

ADDENDUM NUMBER 1

Date: July 12, 2018

Project: Renovation and Expansion of
Ruffini Parking Lot
RFP PK-03-18

Engineer: SKG Engineering, LLC
Firm No.: F-7608

To: Prospective Bidders



This Addendum forms a part of the Contract Documents and modifies the Bidding Document with amendments and additions noted below.

Changes to Civil Engineering Drawings:

Sheet C3.1:

- Note A: The 6" PVC sewer line in Avenue B is "By Others".
- Note B: The water line, meter, and valves are "By Others".
- Note C: The 4" PVC Sewer Service line connection to the building is "By Others".
- Note D: The Transformer and conduits and electric work is "By Others".
- Note F: This work is "By others".
- Note G: The overhead utility lines are to be removed "By Others".
- Note H: This work is "By Others".

END OF ADDENDUM NUMBER 1